

AD-A142 832

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
FOUNTAIN LAKE DAM (CT..(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV MAR 80


1/1

UNCLASSIFIED

F/G 13/13

NL

END
DATE
FILMED
8 84
DTIC X




MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A142 832

NAUGATUCK RIVER BASIN
ANSONIA & SEYMOUR, CONNECTICUT

FOUNTAIN LAKE DAM
CT 00025

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

DISC FILE COPY

MARCH 1980

This document has been approved
for public release and sale in
distribution is unlimited.

84 06 28

FOUNTAIN LAKE DAM
CT 00025

NAUGATUCK RIVER BASIN
ANSONIA/SEYMOUR, CONNECTICUT



CLASSIFICATION	
UNCLASSIFIED	
AUTHORITY	
DATE	
REVISION	
DESCRIPTION	
AVAILABILITY CODES	
Dist.	Avail. and/or Special
A-1	

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

This document has been approved
for public release and sale; its
distribution is unlimited.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00025	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Fountain Lake Dam, NAUGATUCK RIVER BASIN NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1980
		13. NUMBER OF PAGES 80
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Lake, Fountain Naugatuck River, Ansonia & Seymour, Conn.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Dam consists of a mortared stone masonry structure with an upstream earth embankment and an overflow spillway located near the center of the dam. Maximum height is 20 ft. and overall length of 315 ft. The stone masonry wall has a top width of 6 ft., a downstream batter of 1 horizontal to 6.5 vertical and an unknown upstream batter. There's an 18 in. wide by 12 inch concrete wall at the upstream edge of the masonry wall. The spillway consists of a concrete cap on the stone masonry wall. The crest length is 22.3 ft. and the freeboard from spillway crest to the top of the concrete wall is 1.7 ft. The outlet works consist of a 12 inch supply main from an upstream intake structure.		

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

IDENTIFICATION NO: CT 00025
NAME OF DAM: Fountain Lake Dam
TOWN: Ansonia - Seymour
COUNTY AND STATE: New Haven County, Connecticut
STREAM: Unnamed tributary to the Naugatuck River
DATE OF INSPECTION: December 21, 1979

BRIEF ASSESSMENT

The Fountain Lake Dam consists of a mortared stone masonry structure with an upstream earth embankment, and an overflow spillway located near the center of the dam. An earth embankment forms the right end of the dam. The dam has a maximum height of 20 feet, and an overall length of 315 feet. The stone masonry wall has a top width of approximately 6 feet, a downstream batter of 1 horizontal to 6.5 vertical, and an unknown upstream batter. There is an 18-inch wide by 12-inch high concrete wall at the upstream edge of the stone masonry wall. The spillway consists of a concrete cap on the stone masonry wall. The crest length is 22.3 feet and the freeboard from spillway crest to the top of the concrete wall is 1.7 feet. The outlet works consist of a 12-inch supply main from an upstream intake structure or gate chamber to a downstream chemical treatment building. There are high level and low level 16-inch intake sluice gates located on the outside of the upstream wall of the gate chamber. A 30-foot long wooden foot bridge provides access from the dam to the gate chamber.

Based on the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams, the dam is classified as "Small" in size, with a "High" hazard potential. According to the Guidelines, the Test Flood should be in the range of 1/2 the Probable Maximum Flood (1/2 PMF) to the Probable Maximum Flood (PMF). The PMF was selected as the Test Flood. The dam has a watershed of only 0.17 square miles. The inflow was calculated to be 360 cfs and the routed outflow was 335 cfs. The spillway has a capacity of 140 cfs or 42 percent of the routed outflow. The Test Flood routed outflow would overtop the dam by 0.3 feet.

The condition of the dam at the time of inspection was judged to be fair. Conditions that could affect the integrity of the dam are the seepage exiting through the face and downstream of the dam; the erosion of the upstream embankment; the growth of large trees at the toe of the dam; the outlet pipe being controlled by downstream gates instead of upstream sluice gates; and the lack of adequate spillway capacity.


It is recommended that a qualified, registered engineer investigate the seepage and wet areas downstream of the dam and the erosion of the upstream embankment; perform a detailed hydrologic/hydraulic analysis to determine the need for and means to provide additional discharge capacity; and to evaluate the ability of the dam to withstand overtopping if so indicated. The trees at the toe of the dam should be removed and the root zones carefully backfilled with selected soils.

Additionally, the intake sluice gates should be closed, and the foot bridge to the gate chamber repaired. Technical inspections by qualified, registered engineers should be made annually. An operations and maintenance manual should be prepared for the dam and operating facilities, and a formal warning system should be put into effect.

The owner should implement the recommendations as described herein and in greater detail in Section 7 of the Report, within one year after receipt of this Phase I Inspection Report.



Donald L. Smith

Donald L. Smith, P.E.
Project Engineer



Roald Haestad

Roald Haestad,
President



PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the

condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety of the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGES</u>
LETTER OF TRANSMITTAL	i
BRIEF ASSESSMENT	ii - iv
REVIEW BOARD PAGE	v
PREFACE	vi - vii
TABLE OF CONTENTS	viii - x
OVERVIEW PHOTO	xi
LOCATION PLAN	xii

INDEX TO REPORT

<u>DESCRIPTION</u>	<u>PAGES</u>
1. <u>PROJECT INFORMATION</u>	1 - 8
1.1 GENERAL	1
a. AUTHORITY	1
b. PURPOSE OF INSPECTION	1
1.2 DESCRIPTION OF PROJECT	2 - 4
a. LOCATION	2
b. DESCRIPTION OF DAM AND APPURTENANCES	2 - 3
c. SIZE CLASSIFICATION	3
d. HAZARD CLASSIFICATION	3 - 4
e. OWNERSHIP	4
f. OPERATOR	4
g. PURPOSE OF DAM	4
h. DESIGN AND CONSTRUCTION HISTORY	4
i. NORMAL OPERATIONAL PROCEDURE	4
1.3 PERTINENT DATA	5 - 8
2. <u>ENGINEERING DATA</u>	9 - 10
2.1 DESIGN DATA	9
2.2 CONSTRUCTION DATA	9
2.3 OPERATION DATA	9
2.4 EVALUATION OF DATA	9 - 10

DESCRIPTION	PAGES
3. <u>VISUAL INSPECTION</u>	11 - 14
3.1 FINDINGS	11 - 14
a. GENERAL	11
b. DAM	11 - 13
c. APPURTENANT STRUCTURES	13
d. RESERVOIR AREA	14
e. DOWNSTREAM CHANNEL	14
3.2 EVALUATION	14
4. <u>OPERATIONAL AND MAINTENANCE PROCEDURES</u>	15 - 16
4.1 OPERATIONAL PROCEDURES	15
a. GENERAL	15
b. DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT	
4.2 MAINTENANCE PROCEDURES	15
a. GENERAL	15
b. OPERATING FACILITIES	15
4.3 EVALUATION	15 - 16
5. <u>EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES</u>	17 - 20
5.1 GENERAL	17
5.2 DESIGN DATA	17
5.3 EXPERIENCE DATA	17
5.4 TEST FLOOD ANALYSIS	18
5.5 DAM FAILURE ANALYSIS	19 - 20
6. <u>EVALUATION OF STRUCTURAL STABILITY</u>	21
6.1 VISUAL OBSERVATION	21
6.2 DESIGN AND CONSTRUCTION DATA	21
6.3 POST-CONSTRUCTION CHANGES	21
6.4 SEISMIC STABILITY	21

DESCRIPTION	PAGES
7. <u>ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES</u>	22 - 25
7.1 DAM ASSESSMENT	22 - 23
a. CONDITION	22
b. ADEQUACY OF INFORMATION	22
c. URGENCY	23
7.2 RECOMMENDATIONS	23
7.3 REMEDIAL MEASURES	24
a. OPERATION AND MAINTENANCE PROCEDURES	24
7.4 ALTERNATIVES	25

INDEX TO APPENDIXES

APPENDIX	DESCRIPTION	PAGES
A	INSPECTION CHECKLIST	A-1 - A-7
B	ENGINEERING DATA	B-1 - B-3
C	PHOTOGRAPHS	C-1 - C-7
D	HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1 - D-14
E	INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1



OVERVIEW PHOTO

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

FOUNTAIN LAKE DAM - TR. TO NAUGATUCK RIVER

ANSONIA/SEYMOUR, CONNECTICUT

CT 00025

16 JAN '80

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

PROJECT INFORMATION
SECTION 1

1.1 General

a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Roald Haestad, Inc., has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Roald Haestad, Inc. under a letter of November 1, 1979, from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0015 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection

The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interest.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dams.
3. To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location

The dam is located immediately south of Connecticut Route 334, on the corporate boundary of Ansonia and Seymour, on an unnamed tributary to the Naugatuck River. The dam is shown on the Ansonia Quadrangle Map having coordinates of latitude N 41° 21.4' and longitude W 73° 06.0'.

b. Description of Dam and Appurtenant Structures

The Fountain Lake Dam consists of a mortared stone masonry structure with an upstream earth embankment, and an overflow spillway located near the center of the dam. There is an earth embankment at the right end of the dam. The presence of the stone masonry wall within the earth embankment at this location is unknown. The dam has a maximum height of 20 feet and an overall length of 315 feet. The stone masonry wall has a top width of approximately 6 feet, a downstream batter of 1 horizontal to 6.5 vertical, and an unknown upstream batter.

There is an 18-inch wide by 12-inch high concrete wall at the upstream edge of the stone masonry wall. The concrete wall appears to extend into the abutments at each end of the dam. A nine foot long section of the wall is missing near the right end of the dam.

The top width of the upstream earth embankment varies from a maximum width of 10 feet near the left end of the dam to no embankment at all for a 30 foot long section of the dam to the right end of the spillway.

The spillway consists of a concrete cap on the stone masonry wall. The crest length is 22.3 feet and the freeboard from spillway crest to the top of the concrete wall is 1.7 feet. The outlet works consist of a 12-inch supply main from an upstream intake structure or gate chamber to a downstream chemical treatment building. There are high level and low level 16-inch intake sluice gates located on the outside of the upstream wall of the gate chamber. Screens are reported to be located in the gate chamber. A 30 foot long wooden foot bridge provides access from the dam to the gate chamber. A 6-inch blowoff line connected to the 12-inch supply main approximately 110 feet downstream of the dam discharges to the brook below the dam. Records indicate that an old 8-inch connection to another reservoir passes through the dam and has been filled with grout.

A small wood enclosure located at the top of the dam and to the right of the spillway formerly housed some type of instrumentation.

c. Size Classification - "Small"

According to the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams, a dam is classified as "Small" in size if the height is between 25 feet and 40 feet, or the dam impounds between 50 Acre-Feet and 1,000 Acre-Feet. The dam has a maximum height of 20 feet and a maximum storage capacity of 72 Acre-Feet. Therefore, the dam is classified as "Small" in size based on storage capacity.

d. Hazard Classification - "High"

Based on the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams, the Hazard Classification for the dam is "High". A dam failure analysis indicates that a breach of Fountain

Lake Dam would overtop Connecticut Route 334 located 300 feet downstream of the dam by 6 feet; flood approximately 6 homes located 800 feet downstream of the dam; flood a commercial parking lot located 3,000 feet downstream of the dam to a depth of 2 feet; and flood a low area west of Derby Avenue used for the storage of construction equipment. A breach of the dam could result in the loss of more than a few lives, and the economic losses associated with downstream flooding of homes.

e. Owner

Former Owner: The Fountain Lake Water Company

Present Owner: The Ansonia-Derby Water Company
(Formerly The Ansonia Water Company)
230 Beaver Street
Ansonia, Connecticut 06401
(203) 735-1888

f. Operator

Mr. Frederick Elliot, Superintendent
The Ansonia-Derby Water Company
230 Beaver Street
Ansonia, Connecticut 06401
(203) 735-1888

g. Purpose of the Dam

The dam impounds Fountain Lake, a reservoir for public water supply for the Ansonia-Derby Water Company. Water has not been drawn from the reservoir for the past 3-1/2 years.

h. Design and Construction History

There is no information available on the design or construction of the dam. In 1946, the downstream face and toe of the dam were grouted.

i. Normal Operational Procedures

Daily records of the Lake level are maintained. As the reservoir is currently not in use, there are no operational procedures for the dam.

1.3 Pertinent Data

a) Drainage Area

The drainage area consists of 0.17 square miles of rolling, wooded terrain with no development. Another 0.41 square miles of drainage area is tributary via a diversion channel controlled by a 12-inch gate valve. The capacity of the diversion is approximately 6 cfs.

b. Discharge at Damsite

The discharge at the damsite is over a 22.3 foot long overflow spillway. The outlet works consists of a 12-inch supply main from an upstream intake structure to a downstream chemical treatment plant. A 6-inch blowoff line connected to the 12-inch supply main discharges to the downstream channel.

- | | |
|--|---------------------|
| 1. Outlet Works (conduits) Size: | 12-inch supply main |
| Invert Elevation: | 222 (approximate) |
| Discharge Capacity: | 6 cfs* |
| 2. Maximum Known Flood at Damsite: | Unknown |
| 3. Ungated Spillway Capacity
at Top of Dam: | 138 cfs |
| Elevation: | 238 |
| 4. Ungated Spillway Capacity
at Test Flood Elevation: | 180 cfs |
| Elevation: | 238.3 |
| 5. Gated Spillway Capacity
at Normal Pool Elevation: | N/A |
| Elevation: | |
| 6. Gated Spillway Capacity
at Test Flood Elevation: | N/A |
| Elevation: | |
| 7. Total Spillway Capacity
at Test Flood Elevation: | 180 cfs |
| Elevation: | 238.3 |
| 8. Total Project Discharge
at Top of Dam: | 138 cfs |
| Elevation: | 238 |
| 9. Total Project Discharge
at Test Flood Elevation: | 335 cfs |
| Elevation: | 238.3 |

*Capacity of 6-inch blowoff connected to 12-inch supply main.

c. Elevation - Feet Above Mean Sea Level (NGVD)

1. Streambed at Toe of Dam:	218
2. Bottom of Cutoff:	Unknown
3. Maximum Tailwater:	N/A
4. Recreation Pool:	N/A
5. Full Flood Control Pool:	N/A
6. Spillway Crest:	236.3
7. Design Surcharge - Original Design:	Unknown
8. Top of Dam:	238
9. Test Flood Surcharge:	238.3

d. Reservoir - Length in Feet

1. Normal Pool:	800 ft.
2. Flood Control Pool:	N/A
3. Spillway Crest Pool:	800 ft.
4. Top of Dam:	900 ft.
5. Test Flood Pool:	900 ft.

e. Storage - Acre-feet

1. Normal Pool:	63 Ac.-Ft.
2. Flood Control Pool:	N/A
3. Spillway Crest Pool:	63 Ac.-Ft.
4. Top of Dam:	72 Ac.-Ft.
5. Test Flood Pool:	74 Ac.-Ft.

f. Reservoir Surface - Acres

1. Normal Pool:	5.5 Acres
2. Flood-Control Pool:	N/A
3. Spillway Crest:	5.5 Acres
4. Test Flood Pool:	5.5 Acres
5. Top of Dam:	5.5 Acres

g. Dam

- | | |
|---------------------|---|
| 1. Type: | Mortared stone masonry with upstream earth embankment |
| 2. Length: | 315 ft. |
| 3. Height: | 20 ft. |
| 4. Top Width: | 6 ft. |
| 5. Side Slopes: | Downstream - Stone Masonry
1 Horizontal to 6.5 Vertical

Upstream - Earth Embankment
2 Horizontal to 1 Vertical |
| 6. Zoning: | N/A |
| 7. Impervious Core: | N/A |
| 8. Cutoff: | Unknown |
| 9. Grout Curtain: | Unknown |
| 10. Other: | Earth embankment
Right side of dam |

h. Diversion and Regulating Tunnel N/A

i. Spillway

1. Type: Concrete cap with a vertical stone face on the downstream side
2. Length of Weir: 22.3 ft.
3. Crest Elevation
with Flashboards: N/A
without Flashboards: 236.3
4. Gates: N/A
5. Upstream Channel: Reservoir
6. Downstream Channel: Sinuous Stream
7. General: 1.7 feet of freeboard from spillway crest to top of dam

j. Regulating Outlets

1. Invert: 222 (Approximate)
2. Size: 12-inch
3. Description: Supply Main
4. Control Mechanism: 2 - 16-inch x 16-inch manually operated sluice gates at intake. High and low level inlets. Normally controlled by downstream valves.
5. Other: A 6-inch blowoff is connected to the 12-inch supply main.

ENGINEERING DATA

SECTION 2

2.1 Design Data

There was no design data available for review. The only information available on the dam consisted of a contour map of the impoundment dated 1929, a plan prepared by The Penetryn System, Inc. dated June 26, 1946 showing proposed repairs to the dam, and a sketch showing the outlet works piping.

2.2 Construction Data

There was no information available for review on the original construction of the dam. The owner reported that the repair work shown on the 1946 Penetryn plan was not completed on the right side of the dam. The plan calls for "guniting" the top of the dam, re-pointing the stone masonry joints, and grouting of the downstream face and base of the wall.

2.3 Operation Data

The water level in the Lake is recorded daily. Levels above spillway are recorded only as "Running Over".

2.4 Evaluation of Data

a. Availability

Existing data was provided by the Ansonia-Derby Water Company. Original design plans were lost during the August 1955 Flood. A list of available reference material is given in Appendix B.

b. Adequacy

The information that was available along with the visual inspection, past performance history, and hydraulic and hydrologic calculations were adequate to assess the condition of the facility.

c. Validity

The visual inspection and field surveys indicate that the repairs shown on the 1946 Penetryn plan were not completed. The downstream face of the masonry wall to the left of the spillway appears to have been grouted, as grout pipes are exposed. No grout pipes were visible to the right of the spillway.

VISUAL INSPECTION

SECTION 3

3.1 Findings

a. General

The visual inspection of the dam was conducted on December 21, 1969. At the time of the inspection, water was flowing over the spillway. The general condition of the dam at the time of the inspection was fair.

b. Dam

The dam consists of a mortared stone masonry structure, Photos 1 and 2, with an upstream earth embankment and an overflow spillway located near the center of the dam, Photo 3. There is an earth embankment at the right end of the dam, Photo 4. The presence of the stone masonry wall within the embankment at this section of the dam is unknown. An 18-inch wide approximately 12-inch high concrete wall, Photo 4, was observed along the entire length of the dam crest, with the exception of a 9 foot long section near the right end of the dam. It is not known whether this concrete wall on the crest is the top of a core wall or simply a parapet wall to raise the freeboard. The construction of the upstream face of the dam is not known. A varying width of earth embankment was observed upstream of the concrete wall at all locations except for a 30 foot long section immediately to the right of the spillway, Photos 5 and 6, where no earth embankment was observed. It may be that the dam was constructed without an embankment at this section of the dam; however, it is possible that this condition was caused by erosion of the upstream embankment and consequent reduction in crest width. No riprap was

observed on the upstream slope of the earth embankment and erosion was observed at the waterline, Photo 7.

The section of the downstream masonry wall to the right of the spillway was observed to be in good condition. The mortar in the joints was generally tight. However, some seepage through this section of the wall was observed immediately to the right of the spillway, downstream of the area where no earth embankment was observed on the upstream side of the crest. At this location, evidence of seepage in the form of ice, was observed at elevations up to within 3 feet of the crest of the dam, Photo 3.

The section of the downstream masonry wall to the left of the spillway showed evidence of "guniting". The "gunite" was cracked and showed efflorescence in many joints. Grout pipes, 3/4-inch diameter, were also observed protruding from this section of the wall. Evidence of seepage, in the form of ice, was observed in the bottom 5 feet of the wall near the left end, Photo 8. At one location, the rate of seepage from one of the joints was such that ice had not built up. The seeping water appeared to be clear.

Three wet areas were observed downstream of the dam. One wet area approximately 20 feet wide by 35 feet long was observed approximately 30 to 50 feet downstream of the seeps in the base of the left end of the downstream wall. Some of the water in this wet area appeared to originate from clear seepage from the left abutment. A second wet area approximately 10 feet wide by 15 feet long was observed downstream and to the right of the spillway as shown in Figure 2, Appendix B. Seepage with rust staining and an oily sheen was observed in this area. A third wet area consisted of a small stream

flowing in a 15 foot wide gully originating approximately 25 feet to the right of the second wet area described above, Photo 9. The seepage in this gully flowed from the point of origination downstream until it intersected the brook flowing from the spillway. The seepage was rust stained and had an oily sheen. Approximately 25 feet downstream of the section of the dam where the concrete was missing, a 15 foot wide by 20 foot long, 3 to 4 foot deep, dry depression was observed. No explanation of this depression was apparent.

Several pine trees with trunk diameters of approximately 20 inches were observed within approximately 10 feet of the toe of the stone masonry wall on both sides of the spillway, Photos 1 and 2.

c. Appurtenant Structures

The appurtenant structures consist of the spillway and the outlet works. The spillway consists of a concrete cap on the stone masonry portion of the dam. The concrete wall at the left side of the spillway is deteriorated, Photo 10.

The outlet works consists of an intake structure or gate chamber located in the reservoir apparently at the toe of the upstream earth embankment. The concrete is deteriorated and efflorescence is present in some areas, Photo 11. The intake gates appear to be open, with the stems rusted at the waterline. The gates were not operated during the inspection. The owner reported that the gates are operable.

The wooden foot bridge, Photo 4, is in poor condition with many of the deck boards rotted through.

A small wooden enclosure is located at the top of the dam to the right of the spillway, Photo 5. The enclosure formerly housed some type of instrumentation for the dam.

d. Reservoir Area

There were no indications of instability along the edges of the reservoir in the vicinity of the dam.

e. Downstream Channel

The downstream channel consists of a sinuous streambed in a lightly wooded area. Some wood and rock debris were observed in the streambed, particularly at the base of the spillway.

3.2 Evaluation

Based on the results of the visual inspection the dam is judged to be in fair condition. The following conditions could affect the long-term performance of the dam:

- a. Continued seepage through the dam could lead to internal erosion of the dam.
- b. Continued erosion of the upstream face could lead to further loss of crest width, such as that which may have occurred to the right of the spillway. This loss of crest width could increase the amount of seepage through the dam and lead to internal erosion and/or breach of the dam.
- c. The root systems of the large pine trees located near the downstream toe of the dam could provide pathways for seepage and internal erosion.
- d. The fact that the intake gates are open means that the supply main through the dam is under constant pressure, any leaks could lead to internal erosion of the dam.
- e. The poor condition of the wooden foot bridge does not provide adequate access to the intake structure or gate chamber.

OPERATIONAL AND MAINTENANCE PROCEDURES

SECTION 4

4.1 Operational Procedures

a. General

The reservoir is currently not being used. Therefore, there is no formal operational procedures in effect. Water levels are normally recorded daily. The sluice gates at the intake structure or gate chamber are left open. When water is drawn from the reservoir, valves in a downstream chemical treatment plant are opened.

b. Description of Any Warning System In Effect

There is no formal warning system in effect for the dam. The dam is monitored twice a day during heavy rains, and the police would be notified in the event of an emergency.

4.2 Maintenance Procedures

a. General

Normal maintenance procedures for the dam include cutting the brush and grass in the area of the dam.

b. Operating Facilities

The intake structure or gate chamber is reportedly drained and inspected twice a year. At this time the screens within the chamber are also cleaned. The chamber is drained by opening the blowoff that discharges to the downstream channel.

4.3 Evaluation

Present operations and maintenance procedures are inadequate, as is evident by the condition of the service bridge to the gate chamber. An operations and maintenance manual should be prepared for the dam and operating facilities. The warning system now in effect should be formalized and should include monitoring the dam

during heavy rains and procedures for notifying downstream authorities. The dam should be inspected by a qualified, registered engineer every year.

EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

SECTION 5

5.1 General

The spillway for Fountain Lake Dam is a 22.3 foot long overflow section in the middle of the dam. The spillway consists of a concrete cap and vertical stone masonry downstream face. At the crest of the dam is a concrete wall, 18-inches wide by 12-inches high, poured on the stone masonry dam. The top of the concrete wall is 1.7 feet above spillway level.

The dam has a tributary watershed of only 0.17 square miles. The terrain is "rolling" wooded hills with no development. Another 0.41 square mile watershed is tributary via a diversion channel controlled by a 12-inch gate valve. The capacity of the diversion is about 6 cfs. Overtopping of the diversion will not add significant flood flows to Fountain Lake.

Piping at the dam consists of a 12-inch supply main from an upstream intake structure with two 16-inch sluice gates, to a downstream chemical treatment building. Sketches indicate an old 8-inch line through the dam has been filled with grout. The supply main has a 6-inch blowoff to the stream below the dam. The supply main is also connected to the old 8-inch line below where it was grouted. The blowoff has a capacity of 6 cfs.

5.2 Design Data

No design data on the dam or spillway could be found.

5.3 Experience Data

No records of past flood experience were available.

5.4 Test Flood Analysis

Based on the dam failure analysis, the dam is classified as "High" hazard potential. The size of the dam is "Small", based on a height of 20 feet and storage capacity of 72 Acre-Feet. According to the Recommended Guidelines for Safety Inspection of Dams by the Corps of Engineers', the Test Flood should be in the range of 1/2 the Probable Maximum Flood (1/2 PMF) to the Probable Maximum Flood (PMF) depending on the involved risk. A Test Flood equal to the PMF was selected because of the extensive development downstream and the potential loss of more than a few lives should the dam fail. The Test Flood was calculated using 2,125 cubic feet per second per square mile (csm), from the minimum 2 square mile drainage area shown on the guide curves supplied by the Corps of Engineers, and the 0.17 square mile watershed of Fountain Lake Dam. The peak inflow was calculated to be 360 cfs and the routed outflow 335 cfs. The capacity of the diversion was not included in the calculations. The flood routing through the reservoir was done in accordance with "Estimating Effect of Surcharge Storage on Maximum Probable Discharges" provided by the Corps of Engineers.

The spillway capacity was calculated to be 140 cfs or 42% of the Test Flood routed outflow. The Test Flood would overtop the dam by 0.3 feet.

The spillway capacity of this dam appears to be inadequate and overtopping could occur in the future. The construction of the dam may allow for some overtopping without failure of the structure.

An investigation should be made to determine the need for and means to provide additional project discharge capacity.

5.5 Dam Failure Analysis

A dam failure analysis was made using the "Rule of Thumb" guidance provided by the Corps of Engineers. Failure was assumed when the water level reached the top of the dam.

The dam breach would release up to 10,500 cfs into the stream below the dam. The flood wave would travel 300 feet downstream where it would overtop Connecticut Route 334 by 6 feet. The flow would divide at this point with some of the water crossing the road and continuing down the brook and the remainder flowing down Route 334. A portion of this water would flow between the houses on the left side of Route 334 and rejoin the flow in the brook. The rest of the water would continue down the highway and eventually reach the Naugatuck River. The flow in the brook would continue downstream until reaching the shopping plaza where flooding of the parking lot would occur because the culvert does not have the needed capacity. The flood waters in excess of the highway culvert capacity would flow across the parking lot and down to a low area on the west side of Derby Avenue. This area is currently used for storage of construction equipment. The flood waters would pond in the low area and eventually run out to the Naugatuck River through existing culverts.

The maximum spillway capacity, prior to dam breach, of 140 cfs does not exceed the capacity of the downstream culverts. The depth of flow, at the culverts, prior to dam breach is 7.6 feet at Route 334, 6.3 feet at Ansmor Road, 5.7 feet at the shopping plaza and 3 feet at the Derby Avenue-Route 8 culvert. These depths are within

the available freeboard at each culvert. A dam breach will produce flow depths of 6 feet above Route 334, 4.8 feet above Ansmor Road, and 2 to 3 feet at the parking lot of the shopping plaza. The quantity of flow over Route 334 would be 10,200 cfs, 9,300 cfs would flow over Ansmor Road, and 6,500 cfs over the shopping plaza parking lot.

The dam is classified as "High" hazard potential. A dam failure could result in the loss of more than a few lives, and economic loss due to downstream flooding of homes.

EVALUATION OF STRUCTURAL STABILITY
SECTION 6

6.1 Visual Observations

The visual inspection did not disclose any evidences of present structural instability.

The future integrity of the dam could be affected by continued seepage through the dam; continued erosion of the upstream earth embankment; possible development of internal erosion along root systems of trees; possible damage to the structure resulting from uprooting of large trees; and possible leakage from the supply main kept under constant pressure.

6.2 Design and Construction Data

No original design or construction data are available for the dam. Available information on the dam consists of a contour map of the impoundment dated 1929; a drawing prepared by The Penetryn System, Inc. dated June 26, 1946, showing proposed repairs to the dam; and sketches of the outlet work piping. The owner reports that the repairs shown on the 1946 plan were only partially completed.

6.3 Post-Construction History

With the exception of the repairs to the dam in 1946, no known changes have been made since the construction of the dam.

6.4 Seismic Stability

The dam is located in Seismic Zone I and in accordance with the recommended Phase I Inspection Guidelines, does not warrant seismic stability analysis.

ASSESSMENT, RECOMMENDATIONS, & REMEDIAL MEASURES
SECTION 7

7.1 Dam Assessment

a. Condition

On the basis of the visual inspection the dam is judged to be in fair condition. An evaluation of the hydraulic and hydrologic features of the dam determined that the spillway is capable of passing 42 percent of the Test Flood. The dam would be overtopped by 0.3 feet as a result of the Test Flood. The future integrity of the dam could be affected by the following:

1. Continued seepage through the dam and the possible development of internal erosion.
2. Continued erosion of the upstream earth embankment and consequent loss of crest width.
3. The possible development of internal erosion along the root systems of the large pine trees near the downstream toe of the dam. Possible damage to the dam as a result of uprooting of these trees during a storm.
4. Overtopping of the dam due to inadequate spillway capacity.
5. Possible leakage and the development of internal erosion due to supply main being kept under constant pressure.

b. Adequacy of Information

There was no design or construction information available other than the plan for the repairs to the dam dated 1946. Thus, the assessment of the condition of the dam is based solely on the visual inspection, past performance history and the hydraulic and hydrologic calculations performed for this Report.

c. Urgency

The recommendations presented in Sections 7.2 and 7.3 of this Report should be carried out by the owner within one year of receipt of this Report.

7.2 Recommendations

The following recommendations should be carried out under the direction of a qualified, registered engineer:

1. The seepage and wet areas downstream of the dam should be investigated and seepage control systems designed and constructed, as required.
2. The erosion of the upstream face of the dam should be investigated and repairs and restoration of the upstream face, including appropriate erosion protection, should be designed and constructed.
3. The trees and their roots located within 50 feet of the downstream toe of the dam should be removed, and the root zone should be carefully backfilled with selected soil, placed as directed by the engineer.
4. A detailed hydraulic and hydrologic analysis should be performed to determine the need for and means to provide additional project discharge capacity.
5. The ability of the non-overflow section of the dam to withstand overtopping should be investigated if the analysis performed under No. 4, above, indicates overtopping will take place. Special consideration should be given to the section near the right end of the dam where the concrete wall is missing.

7.3 Remedial Measures

a. Operation and Maintenance Procedures

1. The intake sluice gates should be closed when not in use so that the pipeline through the dam is not under constant pressure.
2. The foot bridge to the gate chamber should be repaired to assure access to the gate operators.
3. The deteriorated concrete on the gate chambers and at the left side of the spillway should be repaired.
4. The reservoir level and the volume of seepage through the dam should be measured periodically. A substantial increase or decrease in flow, unrelated to reservoir level, could indicate a potential problem. Monitoring should be done at least monthly for a period of two years and then the monitoring program should be adjusted after the recommendations outlined in Section 7.2 have been carried out.
5. A program of annual inspections by a qualified, registered engineer should be instituted.
6. A formal operations and maintenance manual for the dam and operating facilities should be prepared. Included in the manual should be procedures for drawing down the Lake in case of an emergency utilizing the 12-inch supply main.
7. A formal warning system should be put into effect and should include monitoring the dam during extremely heavy rains and procedures for notifying downstream authorities in the event of an emergency.

7.4 Alternatives

The only practical alternative to the above recommendations is to breach the dam.

APPENDIX A

VISUAL CHECK LIST WITH COMMENTS

VISUAL INSPECTION CHECK LIST PARTY ORGANIZATION

PROJECT: Fountain Lake Dam

DATE: 12/21/79 TIME: 9:00 a.m. WEATHER: Cloudy - 30°

W.S. ELEVATION: 236.4 U.S. N/A D.N.S.

PARTY	DISCIPLINE
1. Donald L. Smith, P.E. - Roald Haestad, Inc.	Civil/Hydrologist
2. Donald G. Litke, P.E. - Roald Haestad, Inc. Geotechnical	Civil Engineer
3. Richard Murdoch, P.E. - Engineers, Inc. Geotechnical	Geotechnical Engineer
4. John W. France, P.E. - Engineers, Inc.	Geotechnical Engineer
5. _____	_____
6. _____	_____

PROJECT FEATURE	INSPECTED BY	REMARKS
1. Dam Embankment	RM, JWF	Erosion upstream, large trees downstream of toe.
2. Intake Structure & Channel	RM, JWF	Channel under water. Structure is control tower or gate chamber.
3. Outlet Works - Control Tower	RGL, DLS	Deteriorated concrete, gates appear to be open.
4. Outlet Works - or Gate Chamber	RGL, DLS	
5. Outlet Works - Outlet Structure & Channel	RM, JWF	No outlet channel or structure.
6. Spill. Weir, App. RM, JWF	RGL, DLS	Good condition, some rock and debris in discharge channel.
7. Outlet Works - & Disch, Channel	RGL, DLS	Poor - needs repair or replacement.
8. Outlet Works - Service Bridge	RGL, DLS	
9. _____	_____	_____
10. _____	_____	_____
11. _____	_____	_____
12. _____	_____	_____

PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam DATE: 12/21/79
 PROJECT FEATURE: Dam Embankment NAME: RM
 DISCIPLINE: Geotechnical Engineer NAME: JWF

AREA ELEVATION	CONDITIONS
DAM EMBANKMENT	
CREST ELEVATION	238
CURRENT POOL ELEVATION	236.4
MAXIMUM IMPOUNDMENT TO DATE	Unknown
SURFACE CRACKS	None observed
PAVEMENT CONDITION	None observed
MOVEMENT OR SETTLEMENT OF CREST	None observed
LATERAL MOVEMENT	None observed
VERTICAL ALIGNMENT	Good
HORIZONTAL ALIGNMENT	Good
CONDITION AT ABUTMENT AND AT CONCRETE STRUCTURES	Good
INDICATIONS OF MOVEMENT OF STRUCTURAL ITEMS ON SLOPES	N/A
TRESPASSING ON SLOPES	None observed
VEGETATION ON SLOPES	Several large (20-in. dia.) pines located within 10' of downstream toe of dam
SLOUGHING OR EROSION OF SLOPES OR ABUTMENTS	Erosion of upstream slope including signi- ficant loss of crest width to the right of the spillway.
ROCK SLOPE PROTECTION - RIPRAP FAILURES	No riprap protection observed
UNUSUAL MOVEMENT OR CRACKING AT OR NEAR TOES	None observed
EMBANKMENT OR DOWNSTREAM SEEPAGE	Seepage exiting downstream masonry wall to the right of spillway and at base of left end. Three wet areas downstream of dam.
PIPING OR BOILS	None observed
FOUNDATION DRAINAGE FEATURES	None known or observed
TOE DRAINS	None known or observed
INSTRUMENTATION SYSTEM	None known or observed

OTHER: Depression at toe of embankment near right end of dam. Section of concrete wall missing at this location.

PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam DATE: 12/21/79
Intake Channel
 PROJECT FEATURE: Outlet Works - and Structure NAME: RM,JWF
 DISCIPLINE: Geotechnical/Civil NAME: RGL,DLS

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
A. <u>APPROACH CHANNEL:</u>	<u>Under water and not observable</u>
<u>SLOPE CONDITIONS</u>	
<u>BOTTOM CONDITIONS</u>	
<u>ROCK SLIDES OR FALLS</u>	
<u>LOG BOOM</u>	<u>None</u>
<u>DEBRIS</u>	<u>None</u>
<u>CONDITION OF CONCRETE LINING</u>	<u>N/A</u>
<u>DRAINS OR WEEP HOLES</u>	
B. <u>INTAKE STRUCTURE:</u>	<u>Intake structure is Control Tower. (Gate Chamber)</u>
<u>CONDITION OF CONCRETE</u>	<u>Fair</u>
<u>STOP LOGS AND SLOTS</u>	<u>N/A</u>

PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam DATE: 12/21/79
Control Tower
 PROJECT FEATURE: Outlet Works - (Gate Chamber) NAME: EGL
 DISCIPLINE: Civil Engineer NAME: DLS

AREA EVALUATED	CONDITIONS
OUTLET WORKS - CONTROL TOWER (GATE CHAMBER)	
A. CONCRETE AND STRUCTURAL:	No building, just chamber
GENERAL CONDITION	Fair
CONDITION OF JOINTS	None observed
SPALLING	Outside of chamber spalled
VISIBLE REINFORCING	None
RUSTING OR STAINING OF CONCRETE	None
ANY SEEPAGE OR EFFLORESCENCE	Efflorescence on outside
JOINT ALIGNMENT	None observed
UNUSUAL SEEPAGE OR LEAKS IN GATE CHAMBER	Could not be observed - Chamber locked.
CRACKS	No major cracks
RUSTING OR CORROSION OF STEEL	Gate stems rusted at water line.
B. MECHANICAL AND ELECTRICAL:	None
AIR VENTS	N/A
FLOAT WELLS	N/A
CRANE HOIST	N/A
ELEVATOR	N/A
HYDRAULIC SYSTEM	N/A
SERVICE GATES	Two intake gates on outside of gate cham- ber appear to be open, and not to have been used in several years.
EMERGENCY GATES	N/A
LIGHTNING PROTECTION SYSTEM	N/A
EMERGENCY POWER SYSTEM	N/A
WIRING AND LIGHTING SYSTEM IN GATE CHAMBER	N/A

PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam DATE: 12/21/79
 PROJECT FEATURE: Outlet Structure
Outlet Works - and Channel NAME: RM, JWF
 DISCIPLINE: Geotechnical/Civil NAME: RGL, DLS

AREA EVALUATED	CONDITIONS
OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL	No outlet channel or structure - Under- ground pipe to downstream treatment building and outlet in stream.
GENERAL CONDITION OF CONCRETE	
RUST OR STAINING	
SPALLING	
EROSION OR CAVITATION	
VISIBLE REINFORCING	
ANY SEEPAGE OR EFFLORESCENCE	
CONDITION AT JOINTS	
DRAIN HOLES	
CHANNEL	
LOOSE ROCK OR TREES OVERHANGING CHANNEL	
CONDITION OF DISCHARGE CHANNEL	

PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam Spillway Weir, Approach DATE: 12/21/79
 PROJECT FEATURE: Outlet Works - & Discharge Channel NAME: RM, JWF
 DISCIPLINE: Geotechnical/Civil NAME: RGL, DLS

AREA EVALUATED	CONDITIONS
OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS	
A. APPROACH CHANNEL:	
GENERAL CONDITION	Good
LOOSE ROCK OVERHANGING CHANNEL	None observed
TREES OVERHANGING CHANNEL	None observed
FLOOR OF APPROACH CHANNEL	Under water and not observable
B. WEIR AND TRAINING WALLS:	
GENERAL CONDITION OF CONCRETE	Good - Some deterioration of left training walls.
RUST OR STAINING	None observed
SPALLING	Some spalling of left training walls.
ANY VISIBLE REINFORCING	None observed
ANY SEEPAGE OR EFFLORESCENCE	None observed
DRAIN HOLES	None observed
C. DISCHARGE CHANNEL:	
GENERAL CONDITION	Fair
LOOSE ROCK OVERHANGING CHANNEL	None observed
TREES OVERHANGING CHANNEL	None observed
FLOOR OF CHANNEL	Sinuuous streambed
OTHER OBSTRUCTIONS	Some rock and wood debris on floor of channel, particularly at base of spillway.


PERIODIC INSPECTION CHECK LIST

PROJECT: Fountain Lake Dam DATE: 12/21/79
 PROJECT FEATURE: Outlet Works - Service Bridge NAME: RGL
 DISCIPLINE: Civil Engineer NAME: DLS

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SERVICE BRIDGE</u>	
A. <u>SUPER STRUCTURE:</u>	
<u>BEARINGS</u>	N/A
<u>ANCHOR BOLTS</u>	N/A
<u>BRIDGE SEAT</u>	N/A
<u>LONGITUDINAL MEMBERS</u>	Rotted wood beams
<u>UNDER SIDE OF DECK</u>	N/A
<u>SECONDARY BRACING</u>	N/A
<u>DECK</u>	Wood deck severely rotted - in need of replacement.
<u>DRAINAGE SYSTEM</u>	N/A
<u>RAILINGS</u>	None
<u>EXPANSION JOINTS</u>	N/A
<u>PAINT</u>	N/A
B. <u>ABUTMENT AND PIERS:</u>	
<u>GENERAL CONDITION OF CONCRETE</u>	Efflorescence, spalling & deterioration of concrete of gate chamber & piers.
<u>ALIGNMENT OF ABUTMENT</u>	Good
<u>APPROACH TO BRIDGE</u>	Good
<u>CONDITION OF SEAT AND BACKWALL</u>	N/A


APPENDIX B

ENGINEERING DATA



PLAN


Scale 1"=40'



ELEVATION

Scale 1"=40'

FIGURE 2



SECTION A-A

Scale 1"=20'

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS


FOUNTAIN LAKE DAM

DRAWN	CHECKED	APPROVED	SCALES AS NOTED
JRS	DLB		DATE FEB 1980 PAGE B-1

LIST OF REFERENCES


The following references are available at the Ansonia-Derby Water Company, 230 Beaver Street, Ansonia, Connecticut.

1. The Ansonia Water Company, Contour Map of Fountain Reservoir, Towns of Ansonia and Seymour, Connecticut, Scale: 1" = 40', 1929.
2. "Proposed Repairs to Fountain Lake Dam, Ansonia, Connecticut, For Ansonia Water Company", by The Penetryn Systems, Inc., Albany, Cleveland, Chicago, June 26, 1946.
3. Sketches of Outlet Works Piping.





SECT AT EAST END
(Scale 1/4" = 1'-0")

DOWNSTREAM ELEVATION
(Scale 1" = 10'-0")



SECTION AT SPILLWAY
(Scale 1/4" = 1'-0")



SECT. AT WEST END
(Scale 1/4" = 1'-0")

ELEVATION


- ① Remove all deteriorated concrete and replace with gunite reinforced with wire mesh.
- ② Re point all joints in present stone masonry.
- ③ Excavate to provide access to face of wall for 2'-0" below ground line.
- ④ Drill grout holes spaced about every 25' over face of wall.
- ⑤ Drill grout holes diagonally into base of wall spaced 5'-0" c.c.
- ⑥ Permeate with pressure grout all holes indicated at ④ & ⑤.

PROPOSED REPAIRS TO
FOUNTAIN LINE DAM, ANSONIA, CONN.
FOR ANSONIA WATER CO.
By THE PENETRATION SYSTEM, INC.
ALBANY, CLEVELAND, CHICAGO

APPENDIX C

PHOTOGRAPHS

FIGURE 2



Denotes Photo Number and Direction in which Photo was Taken

RALD HASTAD, NC WORKING ENGINEERS NATURAL BY CONNECTICUT	US ARMY ENGINEER DIV NEW ENGLAND COMPS OF ENGINEERS WALTHAM, MASS
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	PHOTO LOCATION PLAN FOUNTAIN LAKE DAM MASSACHUSETTS AND SEYMOUR, CONNECTICUT
MEAN PICTURE APPROXIMATE DATE FOR PHOTO TAKEN	SCALE 1" = 100'



PHOTO NO. 1

DOWNSTREAM MASONRY WALL RIGHT OF SPILLWAY.
NOTE PINE TREES DOWNSTREAM OF DAM.



PHOTO NO. 2

DOWNSTREAM MASONRY WALL.
NOTE SPILLWAY, AND PINE TREES DOWNSTREAM OF DAM

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

FOUNTAIN LAKE DAM
TR. TO NAUGATUCK RIVER
ANSONIA/SEYMOUR, CT.
CT 00025
16 JAN '80




PHOTO NO. 3

SPILLWAY FROM DOWNSTREAM.
NOTE SEEPAGE INDICATED BY ICE TO
THE RIGHT OF THE SPILLWAY (LEFT IN PHOTO)



PHOTO NO. 4

CREST OF DAM FROM RIGHT ABUTMENT.
NOTE CONCRETE WALL.

U.S ARMY ENGINEER DIV NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

FOUNTAIN LAKE DAM
TR. TO NAUGATUCK RIVER
ANSONIA/SEYMOUR, CT.

CT 00025
21 DEC '79




PHOTO NO. 5

UPSTREAM FACE OF DAM.
NOTE LACK OF EMBANKMENT UPSTREAM OF
CONCRETE WALL TO THE RIGHT OF THE SPILLWAY.



PHOTO NO. 6*

UPSTREAM FACE OF DAM.
NOTE INTAKE STRUCTURE AND SERVICE BRIDGE.

*16 JAN '80

U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASSACHUSETTS	NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS	FOUNTAIN LAKE DAM TR. TO NAUGATUCK RIVER ANSONIA/SEYMOUR, CT.
ROALD HAESTAD, INC. CONSULTING ENGINEERS WATERBURY, CONNECTICUT		CT 00025 21 DEC '79



PHOTO NO. 7

UPSTREAM FACE OF
DAM AT WATERLINE.
NOTE EROSION OF
EARTH EMBANKMENT.



PHOTO NO. 8

SEEPAGE FROM DOWNSTREAM
MASONRY WALL LEFT OF
SPILLWAY INDICATED BY ICE

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

FOUNTAIN LAKE DAM
TR. TO NAUGATUCK RIVER
ANSONIA/SEYMOUR, CT.

CT 00025

21 DEC '79




PHOTO NO. 9

SEEPAGE FLOWING IN 15 FT. WIDE
GULLY DOWNSTREAM OF THE DAM.



PHOTO NO. 10

DETERIORATION OF CONCRETE WALL
AT LEFT SIDE OF SPILLWAY.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

FOUNTAIN LAKE DAM
TR. TO NAUGATUCK RIVER
ANSONIA/SEYMOUR, CT.

CT 00025
21 DEC '79



PHOTO NO. 11

INTAKE GATE CHAMBER.
NOTE EFFLORESCENCE AND DETERIORATION OF CONCRETE.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ROALD HAESTAD, INC.
CONSULTING ENGINEERS
WATERBURY, CONNECTICUT

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


FOUNTAIN LAKE DAM
TR. TO NAUGATUCK RIVER
ANSONIA/SEYMOUR, CT.

CT 00025

21 DEC '79

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS



WATERSHED MAP

FOUNTAIN LAKE DAM
ANSONIA AND SEYMOUR, CONNECTICUT

SCALE: 1" = 2000'


ROALD HAESTAD, INC.

ANSONIA QUADRANGLE 1972

BY SA DATE 1/30/80 **ROALD HAESTAD, INC.** SHEET NO. 1 OF 12
CONSULTING ENGINEERS
CKD BY CLS DATE 1/30/80 37 Brookside Road - Waterbury, Conn. 06708 JOB # 049-13
SUBJECT MOUNTAIN LAKE DAM - Spillway Capacity

Spillway Elev. = 236.3
Spillway Length = 22.3 ft
TOP OF DAM ELEV. = 238.0

Coeff @ Spillway = 2.8
Coeff @ Conc. Wall = 2.8



FREEBOARD = 1.7 ft

$$\text{SPILLWAY CAPACITY} = CL H^{3/2} = 2.8 (22.3 \text{ ft}) (1.7)^{3/2} \\ = 138 \text{ cfs}$$

Average Elevation at top of Dam = 238
Length of Dam Crest @ Elev 238 = 500 ft.

DEPTH OF FLOW (ft)	SPILLWAY	DAM CREST	TOTAL FLOW (cfs)
0.5	22	0	22
1.0	62	0	62
1.5	115	0	115
1.7	138	0	138
2.0	177	138	315
2.5	247	601	848
3.0	324	1245	1569

BY JLS DATE 2/6/80

ROALD HAESTAD, INC.
CONSULTING ENGINEERS


SHEET NO. 2 OF 12

CKD BY SL DATE 2/18/80

37 Brookside Road - Waterbury, Conn. 06708

JOB NO. 049-13

SUBJECT FOUNTAIN LAKE DAM - SPILLWAY CAPACITY CURVE



BY.....S.V.....DATE...1/18/82..

ROALD HAESTAD, INC.

SHEET NO.....3.....OF 12.....

CONSULTING ENGINEERS

CKD BY.....J.S.....DATE...1/30/82..


37 Brookside Road - Waterbury, Conn. 06708

JOB NO. 049-13.....

SUBJECT FOUNTAIN LAKE DAM - Surge Storage.....

Height Above Spillway (ft)	Surface Area (Acres)	Average Surface Area (Acres)	Storage Capacity (Acres - ft)
0	5.51		0
0.5	5.63	5.57	2.8
1.0	5.74	5.69	5.6
1.5	5.87	5.80	8.5
2.0	6.00	5.94	11.5
2.5	6.12	6.06	14.5
3.0	6.24	6.18	17.6

DATE 2/6/80 ROALD HAESTAD, INC. SHEET NO. 4 OF 12
 CONSULTING ENGINEERS
 CRO BY SL DATE 2/18/80 37 Brookside Road Waterbury, Conn. 06708 JOB NO. 049-13
 SUBJECT FOUNTAIN LAKE DAM - SURCHARGE STORAGE CURVE



BY..... DATE..... 5/10 **ROALD HAESTAD, INC.** SHEET NO. 5 OF 12
CONSULTING ENGINEERS
CKD BY RL DATE 2/11/80 37 Brookside Road - Waterbury, Conn. 06708 JOB NO. 042-12
SUBJECT EQUUNIAIN LAKE DAM - Test Flood

Test Flood = PMF

Drainage Area = 109 acres = 0.17 sq. miles

From Corps of Eng chart for "ROLLING" TERRAIN

MPF = 2,125 cfs/sq mile (2.0 sq. mi. Minimum)

PMF = 2,125 cfs/sq. mi. X 0.17 sq. mi. = 361 cfs

$Q_{P1} = 361$ cfs

$H_1 = 2.2$ ft above Spillway, from Discharge Curve

$STOR_1 = 13$ ac-ft, From Area Capacity Curve

= 1.4" runoff from 0.17 sq. mi.

$Q_{P2} = Q_{P1} (1 - \frac{STOR_1}{19}) = 361 \text{ cfs} (1 - \frac{1.4}{19}) = 334$ cfs

$H_2 = 2.2$ ft

$STOR_2 = 13$ ac-ft

$STOR_{AVE} = \frac{13 + 13}{2} = 13$ ac-ft = 1.4" runoff

$Q_{P3} = Q_{P1} (1 - \frac{STOR_{AVE}}{19}) = 361 \text{ cfs} (1 - \frac{1.4}{19}) = 334$ cfs

$H_3 = 2.2$ ft

Spillway Capacity = $CL H^{3/2}$

= $2.8 (22.3) (1.7)^{3/2}$

= 138 cfs

% of PMF = $(\frac{138}{334}) \times 100 = 41\%$ of PMF

BY S/L DATE 1/8/80

ROALD HAESTAD, INC. SHEET NO. 6 OF 12

CKD BY DIS DATE 1/30/80

CONSULTING ENGINEERS

37 Brookside Road - Waterbury, Conn. 06708

JOB NO. 049-12

SUBJECT FOUNTAIN LAKE DAM - Dam Failure Flood Routing

$S = \text{Reservoir Storage at time of failure} = \text{Storage at Spillway Level} + \text{Free board Storage}$

$$S = 63 \text{ ac ft} + (1.7 \text{ ft} \times 551 \text{ acres})$$

$$S = 72.37 \text{ Ac-Ft. USE } 72 \text{ Ac-Ft.}$$

$$Q_{p1} = \text{Peak Failure Outflow} = \frac{8}{27} W_b \sqrt{g} Y_o^{3/2}$$

$$W_b = \text{Breach Width} - 40\% \text{ of dam length at mid height} \\ = (0.4)(175) = 70 \text{ ft}$$

$$Y_o = \text{Total height from river bed to pool level at failure} \\ = 20 \text{ ft}$$

$$Q_{p1} = \frac{8}{27} (70) \sqrt{32.2} (20)^{3/2} = 10,527 \text{ cfs } \approx 10,500 \text{ cfs}$$

SECTION NO. 1:

Breach Length = 300 ft

Assume 1) storage in the reach is negligible.
2) Culvert capacity is negligible.

$$\therefore Q_{p1} = Q_{p2} = 10,500 \text{ cfs}$$

$$H_2 = 6.0 \text{ ft}$$

At this point it can be assumed that 50% of the flood waters will flow in the stream channel and 50% will flow down Fountain Lake Road. When the flood waters have passed Ansmar Road 75% will be flowing in the stream channel and 25% will continue to flow down Fountain Lake Road, Connecticut ROUTE 334.

BY.....SL.....DATE 2/6/80..... **ROALD HAESTAD, INC.** SHEET NO. 7 OF 12.....
CONSULTING ENGINEERS
CKD BY DL DATE 2/7/80 37 Brookside Road - Waterbury, Conn. 06708 JOB NO. Q42-13.....
SUBJECT FOUNTAIN LAKE DAM - Dam Failure Flood Routing.....

SECTION NO 2 (ANSBOR ROAD) Reach Length = 600 ft

$$Q_{P2} = 10,500 \text{ cfs}$$

$$H_2 = 5.0 \text{ ft} \quad A_2 = 547 \text{ sq ft}$$

$$V_2 = A_2 \times \text{Length} = (547 \text{ ft}^2 \times 600 \text{ ft}) \times \frac{1 \text{ ac-ft}}{43,560 \text{ ft}^3} = 7.53 \text{ use } 8 \text{ ac-ft}$$

V_2 is less than $\frac{1}{2}$ of S \therefore reach is O.K.

$$Q_{P3} (\text{TRIAL}) = Q_{P2} (1 - \frac{V_2}{S}) = 10,500 \text{ cfs} (1 - \frac{8}{12}) = 9,333 \text{ cfs}$$

$$H_3 = 4.7 \text{ ft} \quad A_3 = 500 \text{ sq ft}$$

$$V_3 = A_3 \times \text{Length} = (500 \text{ ft}^2 \times 600 \text{ ft}) \times \frac{1 \text{ ac-ft}}{43,560 \text{ ft}^3} = 6.88 \text{ use } 7 \text{ ac-ft}$$

$$V_{ave} = \frac{V_2 + V_3}{2} = \frac{7 + 8}{2} = 7.5 \text{ ac-ft}$$

$$Q_{P3} = Q_{P2} (1 - \frac{V_{ave}}{S}) = 10,500 \text{ cfs} (1 - \frac{7.5}{12}) = 9,406 \text{ cfs}$$

$$H_3 = 4.8 \text{ ft}$$

SECTION NO 3 Reach Length = 700 sq ft

$$Q_{P3} = 75\% \text{ of } 9,406 \text{ cfs} = 7,055 \text{ cfs}$$

$$H_3 = 5.7 \text{ ft} \quad A_3 = 325 \text{ sq ft}$$

$$V_3 = A_3 \times \text{Length} = (325 \text{ ft}^2 \times 700 \text{ ft}) \times \frac{1 \text{ ac-ft}}{43,560 \text{ ft}^3} = 5.22 \text{ use } 5 \text{ ac-ft}$$

V_3 is less than $\frac{1}{2}$ of S \therefore reach is O.K.

$$Q_{P4} (\text{TRIAL}) = Q_{P3} (1 - \frac{V_3}{S}) = 7,055 \text{ cfs} (1 - \frac{5}{12}) = 6,565 \text{ cfs}$$

$$H_4 = 5.5 \text{ ft} \quad A_4 = 300 \text{ sq ft}$$

$$V_4 = A_4 \times \text{Length} = (300 \text{ ft}^2 \times 700 \text{ ft}) \times \frac{1 \text{ ac-ft}}{43,560 \text{ ft}^3} = 4.82 \text{ use } 5 \text{ ac-ft}$$

$$V_{ave} = \frac{V_3 + V_4}{2} = \frac{5 + 5}{2} = 5 \text{ ac-ft}$$

$$Q_{P4} = Q_{P3} (1 - \frac{V_{ave}}{S}) = 7,055 \text{ cfs} (1 - \frac{5}{12}) = 6,565 \text{ cfs}$$


$$H_4 = 5.5 \text{ ft}$$

BY SL DATE 1/18/80 **ROALD HAESTAD, INC.** SHEET NO. 8 OF 12
CONSULTING ENGINEERS
CKD BY DL DATE 2/7/80 17 Brookside Road - Waterbury, Conn. 06708 JOB NO. 049-13
SUBJECT FOUNTAIN LAKE DAM - Flood Routing



SECTION NO. 1 (FIELD SURVEYED)
SEE FIGURE 5

Scale: 1" = 10' Ver.
1" = 40' Horiz

$L = 300$ ft
 $S = 0.083$
 $n = 0.04$




<u>D</u>	<u>W_P</u>	<u>A</u>	<u>R</u>	<u>S</u>	<u>V</u>	<u>Q</u>
2	69	59	0.86	0.083	9.7	572
5	137	355	2.59	0.083	20.2	7171
8	194	820	4.23	0.083	28.1	23,042



BY SL DATE 2/1/80 **ROALD HAESTAD, INC.** SHEET NO. 9 OF 12
 CKD BY DLS DATE 2/18/80 CONSULTING ENGINEERS
 37 Brookside Road - Waterbury, Conn. 06708 JOB NO. 049-13
 SUBJECT FOUNTAIN LAKE DAM - Flood Routing



SECTION NO 2 (Ansmor Road)

Scale 1" = 40' Horiz
 1" = 5' Vert



$L = 600$ ft
 $S = 0.05$
 $n = 0.04$

<u>D</u>	<u>W_P</u>	<u>A</u>	<u>R</u>	<u>S</u>	<u>V</u>	<u>Q</u>
2	114	116	1.02	0.05	8.4	974
4	152	398	2.62	0.05	15.8	6288
5	154	547	3.55	0.05	19.4	10,612



BY SL DATE 2/6/80

ROALD HAESTAD, INC.
CONSULTING ENGINEERS

SHEET NO. 10 OF 12

CKD BY DLB DATE 2/7/80

37 Brookside Road - Waterbury, Conn. 06708

JOB NO. 049-13



SUBJECT FOUNTAIN LAKE DAM - Flood Routing

SECTION NO 3

Scale: 1" = 40' Horiz
1" = 10' Vert

L = 700 ft
S = 0.086
n = 0.04

<u>D</u>	<u>Wp</u>	<u>A</u>	<u>R</u>	<u>S</u>	<u>V</u>	<u>Q</u>
4	80	160	2.0	0.086	17.3	2,768
6	120	360	3.0	0.086	22.7	8,172
8	160	640	4.0	0.086	27.5	17,600



BY.....S.H...DATE 2/7/80... **ROALD HAESTAD, INC.** SHEET NO. 11 OF 12
CONSULTING ENGINEERS
CKD BY D.A.S. DATE 2/18/80 37 Brookside Road - Waterbury, Conn. 06708 JOB NO. 049-13
SUBJECT FOUNTAIN LAKE DAM - Culvert Copasities

Culvert No 1 - (Route 334)

Reference "Hydraulic Charts for the
Selection of Highway Culverts"
HEC No. 5.

Size - 48" RCP

$H_w \text{ max} - 9 \text{ feet}$

Entrance Type - Square Edge With Headwall

$H_w/D = 2.25$ $Q_{\text{max}} = 170 \text{ cfs}$

Culvert No 2 - (Ansmor Road)

Size - 48" RCP

$H_w \text{ max} - 6.3 \text{ feet}$

Entrance Type - Projecting

$H_w/D = 1.58$ $Q_{\text{max}} = 130 \text{ cfs}$

Culvert No 3 - (Shopping Plaza Parking Lot)

Size - 54" RCP

$H_w \text{ max} - 10 \text{ feet}$

Entrance Type - Projecting

$H_w/D = 2.22$ $Q_{\text{max}} = 210 \text{ cfs}$

Culvert No 4 - (Derby Ave. and Route 8)

Size - 8.5' W x 10' H

$H_w \text{ max} - 20 \text{ feet}$

Wingwall Flare - 30° to 75°

$H_w/D = 2.0$ $Q_{\text{max}} = 1,615 \text{ cfs}$

BY.....SL. DATE 2/7/80. **ROALD HAESTAD, INC.** SHEET NO. 12 OF 12
 CONSULTING ENGINEERS
 CKD BY DLS DATE 2/7/80 37 Brookside Road - Waterbury, Conn. 06708 JOB NO. 049-13
 SUBJECT FOUNTAIN LAKE DAM - Blowoff Capacity


Blowoff consists of a 6" line connected to the 12" main.

Top of dam Elev. 238
 Inv. of blowoff Elev. 202 (Assumed)

Head losses: 1) In the pipe = $f \left(\frac{L}{D} \right) \frac{V^2}{2g}$
 2) 90° bend = $K \frac{V^2}{2g}$ ($K = 0.75$)
 3) Gate Valve = $K \frac{V^2}{2g}$ ($K = 0.25$)
 4) Sudden Contraction = $K \frac{V^2}{2g}$ ($K = 0.37$)

$$\text{Equiv Length} = \left(\frac{D_L}{D_S} \right)^{4.87} = \left(\frac{12}{6} \right)^{4.87} = 29.24$$

29.24' of 12" pipe = 1' of 6" pipe



$$P_A + \frac{V_A^2}{2g} + Z_A - H_L = P_B + \frac{V_B^2}{2g} + Z_B$$


$$0 + 0 + 36 - [886(f) + 0.75 + 0.25 + 0.37] \frac{V^2}{2g} = 0 + \frac{V^2}{2g} + 0$$

$$36 - [886f + 1.37] \frac{V^2}{2g} = \frac{V^2}{2g}$$

Assume $V = 3 \text{ ft/sec} \rightarrow f = 0.0395 \therefore V = 7.9 \text{ ft/sec}$
 $V = 6 \text{ ft/sec} \rightarrow f = 0.0385 \therefore V = 8.0 \text{ ft/sec}$
 $V = 8 \text{ ft/sec} \rightarrow f = 0.0380 \therefore V = 8.0 \text{ ft/sec}$

$$Q = VA = 8 \text{ ft/sec} \left(\pi \left(\frac{1}{4} \right)^2 \right) = 6 \text{ cfs}$$

FIGURE 5



LIMITS OF POTENTIAL FLOODING

FOUNTAIN LAKE DAM
ANSONIA-SEYMOUR, CONNECTICUT

SCALE: 1" = 500'

ROALD HAESTAD, INC.

ANSONIA QUADRANGLE 1972

APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

DATE
FILMED
8